



Josh Metcalf, P.E.
Director

Tim D. Fife, P.E.
County Engineer

Department of Public Works

Administration • Engineering Services • Traffic • Road Maintenance • Real Estate Services • Waste Management

Tacoma Power
Task Assignment #2021-01

EXHIBIT A

County Estimate for Reimbursable Work - Chip Sealing

Road	Description	Areas	Length	Width	Sq Yards	Rock size	Cost / Sq Yd	Estimate
Haul Road	Chip Seal - One application liquid asphalt and rock chips	1	10,824	10.0	12,027	3/8"- #10	\$2.50	\$30,066.67

Description: One application of liquid asphalt and rock chips to the Haul Road, from Bridge 108 near Taidnapam Park, northerly approximately 10,824-feet in length, 10-feet wide (outbound lane), for an approximate total of 12,027-square yards.

Chip Seal
Total Square Yardage - 12,027

This estimate includes brooming of the road.

Subtotal -	\$30,066.67
5% Administrative Charge -	\$1,503.33
<u>Total -</u>	<u>\$31,570.00</u>

Prepared By: 

Checked By: _____

2025 NE Kresky Avenue, Chehalis WA 98532 • 360-740-1123 • Fax: 360-740-1479 • TDD: 360-740-1480

www.lewiscountywa.gov